


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Kearney County. Sec. 23 Twp. 22S Rge. 38W (EX (W))
Location as "NE/CNW/SW" or footage from lines C SE/4 of SW/4
Lease Owner J. M. Huber Corp.
Lease Name Geo. Patterson Well No. 1
Office Address Box 978, Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-15-56 19.
Application for plugging filed 2-15-56 19.
Application for plugging approved 2-15-56 19.
Plugging commenced 2-16-56 19.
Plugging completed 2-16-56 19.
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5003' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1110'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded up to 500'; set plug and cemented with 35 sacks through the drill pipe. Mudded up to 35'; set plug and cemented to base of cellar with 15 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dutch George Drilling Co.
Address Petroleum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF Seward, ss.
W. W. Henson (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Henson
Box 978, Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of February, 19 56

My commission expires 7-27-57

D. F. Key
RECEIVED Notary Public.
STATE CORPORATION COMMISSION

FEB 23 1956 2-23-56

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 23 Twp 22 R 38W
BOOK PAGE 39 LINE 36

DRILLERS LOG

15-093-00003-0000

J.M. Huber Corp. - George Patterson #1

Sec. 23-22 So., -38 W, Kearny County, Kansas

0-136	Top soil and sand
136 - 390	Sand
390 - 459	Shale
459 - 710	Sand
710 - 965	Sand and Shale with lime streaks
965 - 1111	Red beds and anhydrite
1111 - 1430	Red beds
1430 - 1785	Salt and red beds
1785 - 2000	Shale and red beds
2000 - 2450	Red beds
2450 - 2635	Lime and shale
2635 - 2695	Red shale - lime streaks
2695 - 2803	Red beds
2803 - 2955	Shale - lime streaks
2955 - 3055	Shale and red beds
3055 - 3065	Shale
3065 - 3265	Lime
3265 - 3375	Lime and shale
3375 - 3393	Lime
3393 - 3525	Lime and shale
3525 - 3625	Lime
3625 - 3729	Lime and Shale
3729 - 3825	Lime
3825 - 3855	Shale
3855 - 3902	Lime and shale
3902 - 4138	Lime
4138 - 4210	Lime and shale
4210 - 4304	Lime - chalky
4304 - 4467	Lime
4467 - 4535	Lime and shale
4535 - 4660	Lime
4660 - 4668	Cherty Lime
4668 - 4820	Lime
4820 - 4917	Lime and shale
4917 - 4956	Shale
4956 - 5009	Lime

RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1956
CONSERVATION DIVISION
Wichita, Kansas

I, the under-signed, J.S. George, hereby certify that the above is a true Drillers Log on J.M. Huber Corp. George Patterson #1, Section 23-22 So., -38 W, Kearny County, Kansas.

STATE OF Kansas, COUNTY OF Sedgewick, SS.

Subscribed and sworn to before me this 22nd day of February, 1956.

Virginia Muddell
Notary Public

My commission expires August 10, 1957.

PLUGGING
RIG NO. 23-22-38W
LOG PAGE 39 LINE 36