

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
D. S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER <sup>21441</sup> 15-055-21441-0000

LEASE NAME Bosworth

WELL NUMBER #2

1650 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 27 TWP. 22S RGE. 34E (E) or (W)

COUNTY Finney

Date Well Completed 12-3-95

Plugging Commenced 12-17-98

Plugging Completed 12-18-98

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Lario Oil & Gas Company

ADDRESS 301 S. Market Wichita, Kansas 67202

PHONE (316) 265-5611 OPERATORS LICENSE NO. 5214

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 4950'

How depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	1850'	None
				5-1/2"	4950'	2800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each side. Plugged off bottom with sand to 4300' and 5 sks. cement. Shot pipe loose @2800', pulled up to 2600', pumped 50 sks. cement, pulled to 1880', pumped 50 sks. cement and 8 sks. gel, pulled to 650', pumped 40 sks. cement, pulled to 40' and circulated 20 sks. cement to surface. Pulled rest of pipe. Plugging Complete. 60/40 pos. 6% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

RECEIVED  
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lario Oil & Gas Company

STATE OF Kansas COUNTY OF Rice

Mike Kelso (Employee of Operator) or (Operator)

Above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed therewith are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 28th day of December, 1998

Gene Simpson  
Notary Public

My Commission Expires: \_\_\_\_\_

IRENE HERZBERG  
State of Kansas  
My Appt. Exp. Aug. 24, 2001

Form CP  
Revised 05-