

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number

Authority 13 July 81
15-015-20, 261200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name

Woolsey Petroleum Corp.

Complete Address

300 W. Douglas #400, Wichita Kans

Lease Name

Miller

Well No.

1-17

Location

C. NE.

Sec. 17 Twp. 21 Rge. 39 (East) (West)

County

Hamilton

Total Depth

3000'

Abandoned Oil Well

Gas Well

Input Well

SWD Well

D & A

Other well as hereafter indicated

Never Produced

Plugging Contractor

Midwest Casing Pulling

Address

Sublette Kans

License No.

711

RECEIVED
STATE CORPORATION COMMISSION

Operation Completed:

Hour:

4:00 PM

Day:

10

Month:

Aug

Year:

1981

Plugging Operations attended by Agent?

All ☒

Part

None

The above well was plugged as follows:

CONSERVATION DIVISION
Wichita, Kansas

8-12-81

There was 845' of 8 1/2" surface casing.
4 1/2" was set to 2998'. Plug back was
2938'. Perforations were 2755-2745. 1st
plug on bottom with 20 lbs cement 1 lb
Hulls 2nd plug to cover Cheyenne at 1110
with 60 lbs cement. 3rd plug at 780' with
35 lbs cement. Push rubber plug ahead of
780' plug. 4th plug at 210 with 25 lbs
cement. 5th plug at 40-0 with 10 lbs cement

I hereby certify that the above well was plugged as herein stated.

There was 2170' of 4 1/2" salvaged.

INVOICED

Signed: Cherene Thomas
Conservation Division Agent

DATE 9-25-81

WELL NO. 2464W