

15. 075. 10006. 00. 00

CP-3

~~NO~~ KANSAS STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED STATE CORPORATION COMMISSION

SEP 28 1962

CONSERVATION DIVISION Wichita, Kansas

9-28-62

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Champlin Oil & Refining Co.

Complete Address: Box 308 Ellinwood, Kansas

Lease Name Kuykendall Well No. # 7

Location NW NW SE Sec. 5 Twp. 27 Rge. 47 (P) (W)

County Hamilton Total Depth 2875'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Central Pipe Pulling Co.

Address: Great Bend, Kansas License No. 459

Operation Completed: Hour 5 PM Day 26 Month 9 Year 62

The Above well was plugged as follows:

7 5/8" 211' Circulated w/cement. 4 1/2" 2874' Cemented.

Top of peforation 2782'

Plug bottom w/sand and 45 sax.cement 2875' to 2765'

Heavy mud 2765' to 200'

Plug and 35 sax.cement 200' to 70'

Heavy mud 70' to 45'

Plug and 15 sax.cement 45' to surface.

(Company Pump) Pulled 1140' 4 1/2" pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Hugh Scott
Well Plugging Supervisor

DATE 10/3/62
INV. NO. 5983-U