

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

Authority July 13, 1981
API Number 15-075 20,365.00.00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Woolsey Petroleum Corporation
Complete Address 300 W. Douglas #400, Wichita Kans.
Lease Name Mittemeier Well No. 1-21
Location E. NE. SW. Sec. 21 Twp. 22 Rge. 39 (East) (West)
County Hamilton Total Depth 3000'
Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D & A ☐
Other well as hereafter indicated Never Produced.
Plugging Contractor Midwest Casing Pulling
Address Sublette Kans. License No. 766
Operation Completed: Hour: 5:00 PM Day: 2 Month: Sept Year: 19 81
Plugging Operations attended by Agent? All ☐ Part ☒ None ☐

The above well was plugged as follows:

There was 842' of 8 1/8" surface casing C.C.
4 1/2" casing set to 2999'. Plug back was
2950'. Perforations were 2770'-2760'. 1st
plug on bottom with 15 lbs cement /
sh. shells. 2nd plug at 1030' to cover
Cheyenne. With 60 lbs cement. 3rd plug
at 750' with solid bridge with 35 lbs
cement. 4th plug at 40-0 with 10 lbs
cement. There was 2270' of 4 1/2" salvaged.

RECEIVED
STATE CORPORATION COMMISSION

SEP - 8 1981

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Lawrence Thomas

Conservation Division Agent

CONSERVATION DIVISION
Wichita, Kansas

DATE 10/6/81

INV. NO. 7834-W

97.50

15.075.20365.00.00

KANSAS DRILLER'S LOG

LEASE: FRITZEMEIER #1-21
OWNER: WOOLSEY PETROLEUM CORPORATION
SPUD: 2-12-81
COMP: 2-17-81

LOCATION: C NE SW
SECTION 21-22S-39W
HAMILTON COUNTY, KANSAS
CASING: 8 5/8" Set @ 842'
5 1/2" Set @ 2999'

Soils & Sand	843
Sand & Red Bed	2015
Shale & Anhydrite	2525
Shale	2735
Shale & Lime	2790
Shale	2830
Lime & Shale	2970
Lime	3000
R.T.D.	3000

STATE OF KANSAS)
)
COUNTY OF SEDGWICK) ss.

I, William C. Wakefield, do hereby certify that this is a true and correct
Driller's Log on the FRITZEMEIER #1-21, located C NE SW SECTION 21-22S-39W
HAMILTON COUNTY, KANSAS, as shown by the daily drilling reports.

JUL - 1 1981

EARL F. WAKEFIELD, INC. CONSERVATION DIVISION
Wichita, Kansas

By William C. Wakefield
William C. Wakefield

Subscribed and Sworn to before me this 25th Day of February, 1981.

My Appointment Expires:
October 28, 1984

Carol J. Noel
Carol J. Noel Notary Public

