

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

R

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -155-20,635-0000 (of this well)

Operator's Full Name Zenith Drilling Corporation
Complete Address Suite 505, 4th Financial Center, Wichita, Kansas 67202
Lease Name Hall Well No. B-1
Location 150' South of E/2 SE Sec. 14 Twp. 23 Rge. 10 (E) (W) X
County Reno Total Depth 3650'
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated _____

Plugging Contractor Sterling Drilling Company and Halliburton Co.

Address Box 129, Sterling, Kansas License No. _____

Operation Completed: Hour 8:30 PM Day 4 Month January Year 1980

The above well was plugged as follows: 8 5/8" - 253' - cem. circ.

Hole filled with mud. 40 sacks cement pumped through drill pipe at 500'. 25 sacks cement pumped through drill pipe at 240'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 13 sacks cement. Rathole bridged and cemented with 2 sacks.

RECEIVED
STATE CORPORATION COMMISSION

JAN 17 1980

1-17-80

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 1-17-80
NO. 1324-w

15-155-20635-0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - HALL "B" #1
Located: C E/2 SE/4 of Section 14-23S-10W, Reno County,
Kansas

OWNER: Zenith Drilling Corporation
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: December 27, 1979
COMPLETED: January 4, 1980

TOTAL DEPTH: 3650'

LOG

CASING RECORD

0 - 256	Clay, Sand and Red Bed	Ran 6 joints 8 5/8" casing (OD). 241.54' set at 253' K.B. with 250 sacks 60/40 Pozmix with 3% cc. Plug down at 5:00 PM, 12-27-79, by Howco.
256 - 828	Shale	
828 - 3395	Lime and Shale	
3395 - 3650	Lime	Plugged.

Deviation Surveys: 3/4° at 1700'
1° at 3640'

RECEIVED
STATE CORPORATION COMMISSION
JAN - 8 1980
CONSERVATION DIVISION
Wichita, Kansas