

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 14 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Texaco Inc.

Complete Address: 614 Bitting Bldg. Wichita, Kansas

Lease Name Garden City Gas Unit Well No. C-1

Location C EL NE NE Sec. 19 Twp. 22 Rge. (E) (W) 33

County Finney Total Depth 2635'

Abandoned Oil Well      Gas Well x Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Sargent Casing Pulling Service

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 4:30 PM Day 11 Month 4 Year 64

The Above well was plugged as follows:

10 3/4"-511' Circulated w/cement. 7"-2635' Cemented

Plug back to 2580' Top perforations 2536'

Plug bottom w/35 Sax.cement, top cement 2300' Mud 2300' to 700'

20 Sax.cement 700' to 600' Mud 600' to 50'

10 Sax.cement 50' to 0 No pipe pulled. Company pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 4/15/64

INV. NO. 8962-W