

15-055-10771-0000

Form CP-3
Rev. 6-26-62

MP
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 3 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Texaco Inc.

Complete Address: 614 Bitting Bldg. Wichita, Kansas

Lease Name O.J. Walters "B" Well No. # 1

Location C SW NW Sec. 22 Twp. 22 Rge. (E) (W) 33

County Finney Total Depth 4800'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Gasing Pulling Company

Address: Chase, Kansas License No. 436

Operation Completed: Hour 4 PM Day 31 Month 12 Year 62

The Above well was plugged as follows:

8 5/8" 397' Circulated w/cement. 4 1/2" 4800' Cemented.

Plug back to 4760' Top perforations- 4715'

Sand 4760' to 4700' 3 sax.cement 4700' to 4660'

Mud 4660' to 375' Plug and 35 sax.cement 375' to 275'

Mud 275' to 50' Rock bridge 50' to 45'

15 sax.cement 45' to surface. Pulled 2980' 4 1/2" pipe.

Company pump. Weld cap on surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Frank Scott*
Well Plugging Supervisor

DATE 1/4/63

INV. NO. 63684