

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 083- 20,582-0000 (of this well)

Operator's Full Name Mack Oil Co.

Complete Address 908 Union Center, Wichita, Kansas

Lease Name Williams Well No. 1

Location C NW NE Sec. 21 Twp. 22 Rge. (E) (W) 25

County Hodgeman Total Depth 4760'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Rains & Williamson Drlg.

Address Wichita, Ks. License No.     

Operation Completed: Hour 11:45 A Day 21 Month 3 Year 1978

The above well was plugged as follows:

RTD 4760' 8 5/8 csg.set 360' cwc Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.

Heavy mud to 300' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
3-24-78  
MAR 24 1978

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3-24-78

INV. NO. 6991-U

Signed: Leo Massey  
Well Plugging Supervisor