



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 117-44

LOCATION NW-NW-NE

SEC. 24 TWP. 22 RGE. 25-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease J. W. Ness

Operator W. B. M. Langdon Address Barnard - Kansas

Field _____ County Woods RECEIVED

Total Depth 5225 Feet.

OCT 18 1949
10-18-49

(Describe briefly the manner in which the well was plugged)

Surface Pipe 15 1/2 - 132 ft. Circulated with cement -

10 3/4 - 1745 ft - Circulated with cement -

7" set at 15190 - Mud from bottom to 4290 ft. Set R. Bridge

& 6 sacks of cement in the 7" casing at 4290 ft. Picked off

& pulled the 7" casing - Filled with mud to 2900 ft. Pack

Bridge & 90 sacks of cement at 2900 ft. Mud to 30 ft.

Bridge & 10 sacks of cement at the surface.

A. & S. Pipe Pulling Co
Plugging Contractors

C. M. Stouffer
District Conservation Agent

Date 10-16-49

PLUGGING
FILE SEC 24 T 22 R 29
BOOK PAGE 117 LINE 44