

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1974
6-18-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Kewanee Oil Company

Complete Address Box 2093, Wichita, Kansas 67201

Lease Name Red Well No. 2W

Location C NE SW NE Sec. 22 Twp. 22 Rge. 25 XE (W)

County Hodgman Total Depth 4700'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 4:00PM Day 13 Month 6 Year 1974

The above well was plugged as follows:

8 5/8" to 559' circulated w/ cement. 5 1/2" to 4691' cemented

Top perforations 4600' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4550' Mud 4550' to 800'

Spotted 35 sacks cement 800' to 700' Mud 700' to 500'

Spotted 35 sacks cement 500' to 400' Mud 400' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'. Halliburton Pump Truck

Pulled 3020' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

NOTICED

Signed: [Signature]
Well Plugging Supervisor

DATE 6/18/74

INV. NO. 9321-W