

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

6-18-74

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Kewanee Oil Co.

Complete Address Box 2093, Wichita, Kansas 67201

Lease Name Red Well No. 1

Location G NE NW NE Sec. 22 Twp. 22 Rge. 25 (E) (W)

County Hodgeman Total Depth 4703'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 2:30PM Day 13 Month 6 Year 1974

The above well was plugged as follows:

8 5/8" to 551' circulated w/ cement. 5 1/2" to 4690' cemented.

Top perforations 4604' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4500' Mud 4500' to 800'

Spotted ³⁵ ~~35~~ sacks cement 800' to 700' Mud 700' to 500'

Spotted 35 sacks cement 500' to 400' Mud 400' to 40'

Plug, Hulls & 10 sacks cement 40' to 0' Halliburton Pump Truck

Pulled 2416' of 5 1/2" casing.

INVOICED hereby certify that the above well was plugged as herein stated.

DATE 6/18/74

INV. NO. 9320-W

Signed: [Signature]
Well Plugging Supervisor