

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-011-22990-00-00
Spot: W2SESE Sec/Twnshp/Rge: 24-25S-23E
660 feet from S Section Line, 1100 feet from E Section Line
Lease Name: COLLINS Well #: 24-44
County: BOURBON Total Vertical Depth: 601 feet

Operator License No.: 33397
Op Name: RUNNING FOXES PETROLEUM INC.
Address: 4B INVERNESS CT E. SUITE 120
ENGLEWOOD, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	591		70 SX
SURF	8.625	22		4 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 10/26/2016 12:00 AM
Plug Co. License No.: 34430 Plug Co. Name: CST OIL & GAS CORPORATION
Proposal Rcvd. from: CHUCK HUTTON Company: _____ Phone: (620) 829-5307

Proposed Plugging Method: Plug well from TD to surface with Portland cement.

Plugging Proposal Received By: RYAN DULING WitnessType: NONE
Date/Time Plugging Completed: 10/26/2016 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 4.5" casing that was cemented inside the 8.625" surface casing to TD. Pumped and circulated cement through the 1" pipe inside the 4.5" casing from TD to surface. Pulled the 1" pipe out of the well and topped the well off with cement. A total of 60 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED
KCC DIST #3
NOV 08 2016
CHANUTE, KS

RD

Remarks:

Plugged through: TBG

District: 03

Signed _____

KCC WICHITA

NOV 14 2016

RECEIVED

(TECHNICIAN)

NOV 21 2016

no

Form CP-2/3

11-14-16