

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-011-22989-00-00  
Spot: NWNE Sec/Twnshp/Rge: 19-25S-23E  
688 feet from N Section Line, 2315 feet from E Section Line  
Lease Name: YEAGER Well #: 19-41  
County: BOURBON Total Vertical Depth: 657 feet

Operator License No.: 33397  
Op Name: RUNNING FOXES PETROLEUM INC.  
Address: 4B INVERNESS CT E. SUITE 120  
ENGLEWOOD, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	651		80 SX
SURF	8.625	20		4 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/26/2016 12:00 AM  
Plug Co. License No.: 34430 Plug Co. Name: CST OIL & GAS CORPORATION  
Proposal Rcvd. from: CHUCK HUTTON Company: \_\_\_\_\_ Phone: (620) 829-5307

Proposed Plugging Method: Plug well from TD to surface with Portland cement.

Plugging Proposal Received By: RYAN DULING Witness Type: NONE  
Date/Time Plugging Completed: 10/26/2016 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe down the inside of the 4.5" that was cemented inside the 8.625" surface casing to TD. Pumped and circulated cement through the 1" pipe inside the 4.5" casing from TD to surface. Pulled the 1" pipe out of the well and topped the well off with cement. A total of 65 sacks of portland cement was reported used to plug this well.

RECEIVED  
KCC DIST #3  
NOV 08 2016  
CHANUTE, KS

RD

Remarks:

Plugged through: TBG

District: 03

Signed [Signature] E.C.R.S.  
(TECHNICIAN)

KCC WICHITA

NOV 14 2016

RECEIVED

NOV 21 2016

720

Form CP-2/3