

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-011-23081-00-00
Spot: NWNE Sec/Twnshp/Rge: 31-26S-23E
768 feet from N Section Line, 2187 feet from E Section Line
Lease Name: GOBL Well #: 2-31
County: BOURBON Total Vertical Depth: 706 feet

Operator License No.: 33397
Op Name: RUNNING FOXES PETROLEUM INC.
Address: 4B INVERNESS CT E. SUITE 120
ENGLEWOOD, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	704		93 SX
SURF	8.625	20		20 SX
T1	2.375	702		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 10/27/2016 12:00 AM
Plug Co. License No.: 34430 Plug Co. Name: CST OIL & GAS CORPORATION
Proposal Rcvd. from: CHUCK HUTTON Company: _____ Phone: (720) 889-0510

Proposed Plugging Method: Plug well from TD to surface with Portland cement.

Plugging Proposal Received By: RYAN DULING Witness Type: NONE
Date/Time Plugging Completed: 10/27/2016 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 4.5" casing that was cemented inside the 8.625" surface casing to TD. Pumped and circulated cement through the 1" pipe inside the 4.5" casing from TD to surface. Pulled the 1" pipe out of the well and topped the well off with cement. A total of 70 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
569	572		
563	566		
549	552		
543	547		

RECEIVED
KCC DIST # 3
NOV 08 2016
CHANUTE, KS

RD

Remarks:

Plugged through: TBG

District: 03

Signed [Signature] E.C.R.S.

KCC WICHITA

(TECHNICIAN)

NOV 14 2016
RECEIVED

11-14-16

NOV 21 2016
700