

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-21189-00-00
Spot: SENWSENW Sec/Twnshp/Rge: 31-13S-19W
1930 feet from N Section Line, 1720 feet from W Section Line
Lease Name: RIEDEL Well #: 2
County: ELLIS Total Vertical Depth: 3894 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3893		125 SX
SURF	8.625	245		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/03/2016 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. DBA Phone: (620) 275-2963

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement, 13 sx gel and 500 # hulls.
DV Tool at 1519' w/325 sx cement.
Perforations: 3838' - 3841'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/03/2016 1:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service ran in hole with tubing to 3610' and pumped 13 sx gel followed by 50 sx cement w/300 # hulls mixed in. Pulled tubing to 2050'. Swift rigged to tubing and pumped 185 sx cement w/200 # hulls mixed in to circulate cement to surface. Pulled tubing. Topped off 5 1/2" casing with 50 sx cement. Hole standing full. Visually checked 8 5/8" casing and it was full of cement.

GPS: 38.87984 -099.47849

Perfs:

Top	Bot	Thru	Comments
3838	3841		

Remarks: SWIFT SERVICES TICKET # 29469

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

KCC WICHITA

CM

OCT 04 2016

OCT 31 2016
RECEIVED

NOV 21 2016 Form CP-2/3

No