

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-21619-00-00
Spot: NW Sec/Twushp/Rge: 32-33S-38W
3979 feet from S Section Line, 3940 feet from E Section Line
Lease Name: GREGORY C Well #: 2
County: STEVENS Total Vertical Depth: 6455 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5800		WITH 2 SX CMT
PROD	5.5	6428	0	WITH 235 SX CMT
SURF	8.625	1737		WITH 815 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/15/2016 10:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Recvd. from: DICK SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: SET CIBP @ 5810' WITH 2 SX CMT. PERFORATE AT 1790' WITH 50 SX CMT (HULLS IN LAST 25 SX).
PERFORATE AT 600' WITH CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/15/2016 12:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

SET CIBP @ 5800' WITH 2 SX CMT. PERFORATE AT 1787' & PUMP 450 SX CMT TO 0'.


Top	Bot	Thru	Comments
5857	5867		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
NOV 16 2016
KCC DODGE CITY

NOV 21 2016
720
kms