

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-185-21133-00-00
 Spot: SWSWSE Sec/Twnshp/Rge: 35-21S-13W
348 feet from S Section Line, 2300 feet from E Section Line
 Lease Name: MATTIE GATES B Well #: 10
 County: STAFFORD Total Vertical Depth: 3800 feet

Operator License No.: 4967
 Op Name: BERENERGY CORPORATION
 Address: PO BOX 5850
DENVER, CO 80217

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3285		WITH 2 SX CMT
PROD	5.5	3800	780	WITH 250 SX CMT
SURF	8.625	428		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/20/2016 10:00 AM
 Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
 Proposal Rcvd. from: DAVID BRADEN Company: BERENERGY CORPORATION Phone: (303) 969-9610

Proposed Plugging Method: CIBP @ 3290' WITH 2 SX CMT. PLUG AT 775' WITH 10 SX GEL & 50 SX CMT. PLUG AT 465' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 10/20/2016 2:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 3285' WITH 2 SX CMT ON TOP. 1ST PLUG AT 775' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 475' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3669	3687		
3335	3500		

Remarks: USED 60/40 POZMIX 4% GEL BY GRESSEL OILFIELD SERVICE.

Plugged through: TBG

District: 01

Signed *Ken Scofield*
 (TECHNICIAN)

RECEIVED
 OCT 25 2016
 KCC DODGE CITY

NOV 21 2016 Form CP-2/3
 70