

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-20594-00-00
Spot: NESWNESE Sec/Twnshp/Rge: 10-17S-24W
1891 feet from S Section Line, 770 feet from E Section Line
Lease Name: AMSTUTZ - AB Well #: 1
County: NESS Total Vertical Depth: 4545 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4516	0	WITH 100 SX CMT
SURF	8.625	216		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/03/2016 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED OFS, LLC
Proposal Revd. from: NEIL PFANNENSTIEL Company: CITATION OIL & GAS Phone: (785) 625-4052

Proposed Pumping Method: PUMP 35 SX CMT & 100# HULLS. TEST CASING TO 300#. OF HOLD PERFORATED AT 1800' & PUMP 50 SX CMT (25 SX WITH HULLS & 25 SX WITHOUT HULLS). PERFORATE AT 1000' & PUMP 80 SX CMT OVER CASING VOLUME. IF IT DOESN'T CIRCULATE PUMP 150 SX CMT DOWN BACKSIDE IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/03/2016 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RAN TBG TO 4400' & PUMPED 100 SX CMT WITH 300# HULLS. PULLED TBG & TEST CASING TO 500#. PERFORATED AT 1800' & PUMPED 85 SX CMT & 100# HULLS. PERFORATED AT 1000' & PUMPED 175 SX CMT & 150# HULLS. TIED ONTO BACKSIDE & PUMPED 35 SX CMT. PRESSURED TO 500# & HELD. TOPPED OFF WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4462	4477		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Michael Maier
5A

(TECHNICIAN)

RECEIVED
NOV - 8 2016
KCC DODGE CITY

MM

NOV 21 2016

720

Form CP-2/3