

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25040-00-00
Spot: NESESW Sec/Twnslp/Rge: 1-17S-22W
1100 feet from S Section Line, 2322 feet from W Section Line
Lease Name: BARBER "A" Well #: 1-1
County: NESS Total Vertical Depth: 4287 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1550		WITH 175 SX CMT
PROD	5.5	4286	0	WITH 175 SX CMT
SURF	8.625	221		WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/07/2016 10:30 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Revd. from: BRIAN KARLIN Company: DOWNING-NELSON Phone: (785) 621-2610

Proposed Plugging Method: PUMP BOTTOM WITH 50 SX CMT & 100# HULLS. PULL TO 1600' & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/07/2016 1:15 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

Perfs:

PUMPED BOTTOM WITH 50 SX CMT & 100# HULLS. PRESSURED TO 900#. PULLED TO 1592' & CIRCULATED CMT TO SURFACE WITH 150 SX CMT. PULLED TBG & TOPPED OFF WITH 20 SX CMT. FILLED BACKSIDE WITH 10 SX CMT.

Top	Bot	Thru	Comments
4282	4285		
4275	4277		

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL CEMENTING.

Plugged through: TBG

District: 01

Signed Larry Harris FCS
(TECHNICIAN)

RECEIVED
NOV 15 2016
KCC DODGE CITY

NOV 21 2016
720
KMS
Form CP-2/3