

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-033-20738-00-00  
Spot: W2NESW Sec/Twnshp/Rge: 32-32S-16W  
2039 feet from S Section Line, 3822 feet from E Section Line  
Lease Name: GARTEN Well #: 1-32  
County: COMANCHE Total Vertical Depth: 5000 feet

Operator License No.: 4581

Op Name: EXOK, INC.

Address: 6410 B N SANTA FE  
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4900		WITH 2 SX CMT
PROD	4.5	5004	0	WITH 100 SX CMT
SURF	8.625	401		WITH 250 SX CMT

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 11/01/2016 9:50 AM

Plug Co. License No.: 8733

Plug Co. Name: DUNKIN, JERRY, INC.

Proposal Revd. from: JERRU DUNKIN

Company: DUNKIN, JERRY, INC.

Phone: (580) 237-6152

Proposed  
Plugging  
Method:

SET BP. TEST CASING IF PRESSURES UP PERFORATE. IF NOT PERFORATING RUN TBG & CIRCULATE.

Plugging Proposal Received By: SCOTT ALBERG

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 11/01/2016 1:30 PM

KCC Agent: SCOTT ALBERG

Actual Plugging Report:

Perfs:

CIBP @ 4900' WITH 2 SX CMT ON TOP. LOAD HOLE AFTER SETTING CIBP. PRESSURE TO 200#, HELD. PERFORATE AT 900'. PUMP 350 SX CMT. TRACES OF CMT AT SURFACE. TIE ON 8 5/8" X 4 1/2" 1/4 BBL AT 100#. TOP OFF WITH 4 SX CMT.

Top	Bot	Thru	Comments
4942	4954		

Remarks: USED CLASS A CEMENT BY JERRY DUNKIN.

Plugged through: CSG

District: 01

Signed

(TECHNICIAN)

RECEIVED  
NOV - 7 2016  
KCC DODGE CITY

NOV 21 2016

Form CP-2/3