

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22160-00-00
Spot: S2S2NE Sec/Twnshp/Rge: 26-32S-12W
3007 feet from S Section Line, 1321 feet from E Section Line
Lease Name: KINKAID Well #: A-1
County: BARBER Total Vertical Depth: 3700 feet

Operator License No.: 4581

Op Name: EXOK, INC.

Address: 6410 B N SANTA FE
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3424		WITH 2 SX CMT
PROD	4.5	3664	0	WITH 100 SX CMT
SURF	8.625	272		WITH 165 SX CMT

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 11/03/2016 8:00 AM

Plug Co. License No.: 8733

Plug Co. Name: DUNKIN, JERRY, INC.

Proposal Revd. from: JERRY DUNKIN

Company: DUNKIN, JERRY, INC.

Phone: (580) 237-6152

Proposed
Plugging
Method:

SET CIBP @ 3424' WITH 2 SX CMT. PERFORATE AT 600'. CIRCULATE CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/03/2016 9:15 AM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

SET CIBP @ 3424' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER.
PRESSURE TEST CASING TO 400#. HOLDING. PERFORATED AT 600'. PUMP DOWN
4 1/2" CASING WITH 244 SX CMT. CMT CIRCULATED TO SURFACE UP
CASING/SURFACE PIPE ANNULUS.

Top	Bot	Thru	Comments
3474	3494		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED CLASS A CEMENT BY JERRY DUNKIN.

Plugged through: CSG

District: 01

Signed

Steve Pfeifer
SA

(TECHNICIAN)

RECEIVED
NOV 10 2016
KCC DODGE CITY

NOV 21 2016
720

Form CP-2/3