

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-21290-00-00
Spot: E2NENW Sec/Twnshp/Rge: 29-15S-13W
4620 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SELLENS E Well #: 4
County: RUSSELL Total Vertical Depth: 2511 feet

Operator License No.: 34278
Op Name: SHAWN D. EVANS INC. DBA ACE OIL C
Address: 18529 WALTERS RD PO BOX 606
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2511		125 SX
SURF	8.625	214		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2016 10:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: SHAWN D. EVANS Company: ACE OIL COMPANY Phone: (785) 324-0502

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/600 # hulls.
June 2005 well was squeezed at 400 - 480' w/200 sx cement. Drilled out and was abandoned by the previous operator (Star Schlobohm Oil Operations KLN 4952).

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/05/2016 6:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

10/03/2016 - Ran in with bit and stacked out. Started to drill with swivel and mud pump. Had good circulation of iron sulfide and blue-gray mud balls in the sample. Circulated hole clean and pulled out bit.
10/05/2016 - Ran in with drill collar and bit and only made about 10'. Could be out of the pipe. Pulled drill collars and ran an impression block with a small mark on the side. Ran in with a diagonal cut on the first joint. Worked the tubing up and down turning all the time. Pulled out of hole and ran in with a tapered mill. Rough spot 4 to 5 joints down. Worked it through. At the bottom the mill kept hanging up when putting any weight on it. Not making any hole and nothing in the samples.
Ran tubing to 450' and pumped 45 sx cement. Circulated cement to the pit. POOH. Hooked to 5 1/2' casing and pumped cement pressured to 750 - 800 psi. Shut in. Hooked to braden head and pumped 35 sx cement at 150 psi. Cement started to come up in the cellar.
10/06/2016 - Visually checked hole, cement down about 25 - 30'.

GPS: 38.72405 -098.79247

Perfs:

Top	Bot	Thru	Comments
2416	2426		

Remarks: QUALITY CEMENTING TICKET # 1748

Plugged through: TBG

District: 04

Signed Ray A Dinkel
KCC WICHITA (TECHNICIAN) CM

OCT 31 2016
RECEIVED

NOV 21 2016
no

OCT 18 2016

Form CP-2/3