

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-05955-00-00  
Spot: SESENE Sec/Twnshp/Rge: 28-11S-17W  
2970 feet from S Section Line, 330 feet from E Section Line  
Lease Name: FA BEMIS A Well #: 5  
County: ELLIS Total Vertical Depth: 3591 feet

Operator License No.: 34405  
Op Name: E & B NATURAL RESOURCES MANAG  
Address: 2501 280TH AVE  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	16	30		35 sx
PROD	7	2575		150 SX
SURF	10.75	1284		50 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/19/2016 9:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: TOM KARST Company: E & B NATURAL RESOURCES MA Phone: (785) 639-6309

Proposed Plugging Method: Ordered 780 sx 60/40 pozmix 4% gel cement, 21 sx gel, 500 # hulls and 75 sx common cement 3% CC.  
PBTD - 3473'.  
TOF - 3370 with unknown tool in hole.  
Arb - OH; 3575' - 3591'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/19/2016 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Gemini perforated at 1230'. E & B ran in hole with tubing to 3305' and pumped 21 sx gel followed by 75 sx 60/40 pozmix 3% cc with 300 # hulls mixed in. Pulled tubing to 1654' and pumped 270 sx w/200 # hulls mixed in to circulate cement up 7" casing. Pulled tubing. Rigged to 7" casing with a swedge and pumped 100 sx cement to circulate cement up 10 3/4" casing. Shut in. 16" full of cement.

GPS: 39.06791 -099.20524

Remarks: QUALITY OILWELL CEMENTING TICKET # 3052

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

  
(TECHNICIAN)

KCC WICHITA

NOV 21 2016

CM

OCT 21 2016

OCT 31 2016

RECEIVED

No

Form CP-2/3