

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-193-20968-00-00  
Spot: NWSWNENE Sec/Twnshp/Rge: 10-7S-36W  
943 feet from N Section Line, 1176 feet from E Section Line  
Lease Name: LYMAN Well #: 1-10  
County: THOMAS Total Vertical Depth: 4598 feet

Operator License No.: 35147  
Op Name: GULF EXPLORATION, LLC  
Address: 9701 N. BROADWAY EXTENSION  
OKLAHOMA CITY, OK 73114

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4643		
SURF	8.625	334		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/11/2016 2:30 PM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: JIM MORRISON Company: GULF EXPLORATION LLC Phone: (308) 737-6147

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement 900 # gel and 300 # hulls.  
8 5/8" surface casing set at 334' w/270 sx cement.  
5 1/2" production casing set at 4643' w/110 sx cement.  
DV Tool set at 3120' w/425 sx cement.  
TD 4595'. PBTD 4586'.  
Perforations: 4346' - 4351', 4420' - 4424', 4464' - 4468'.  
CIBP set at 4410' and 4459'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/11/2016 7:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

TIH with tubing to 4320' and pumped 900 # gel followed by 60 sx cement w/250 # hulls.  
TOOH with tubing to 3120' and pumped 155 sx cement. TOOH with tubing to 1560' and  
pumped 150 sx cement. Circulated cement to surface. TOOH with tubing to surface.  
Connected to 5 1/2" casing and pumped 30 sx cement. Connected to 8 5/8" surface casing and  
pumped 15 sx cement. Pressured to 300 psi.

GPS: 39.46561N -101.31966W

Remarks: ALLIED OILFIELD SERVICES LLC TICKET # 68,122

Plugged through: TBG

District: 04

Signed Darrel Dipman

KCC WICHITA

(TECHNICIAN)

CM

OCT 31 2016

NOV 21 2016

no

Form CP-2/3

RECEIVED