

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-24256-00-00
Spot: SESESW Sec/Twnshp/Rge: 36-33S-14E
339 feet from S Section Line, 2841 feet from E Section Line
Lease Name: EAST LUCKYBECK Well #: Q-24
County: MONTGOMERY Total Vertical Depth: 1291 feet

Operator License No.: 8501
Op Name: HARDIN, JAMES L. DBA HARDIN OIL
Address: 124 OAK LN
CANEY, KS 67333

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1291		195 SX
SURF	8.625	50		15 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/10/2016 12:00 AM
Plug Co. License No.: 31696 Plug Co. Name: CUNNINGHAM CRUDE, A GENERAL PARTNERSHIP
Proposal Rcvd. from: JIM HARDIN Company: _____ Phone: (620) 879-5634

Proposed Plugging Method: run pipe to td and mix and load hole with gel then spot 50' plug pull pipe to 700' spot 50' plug pull pipe to 250' fill to surface with portland.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2016 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Operator had cemented 2 7/8' liner in well September 23, 2010 with 75 sacks of Class A cement. No ACO1 filed. Ran 1" to 1375' gelled hole and spotted 3 sack plug. Pulled up to 500' and spotted 2 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 22 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1252	1261		
RECEIVED KCC DIST #3 NOV 15 2016 CHANUTE, KS DS 11-18-16 KCC WICHITA			

Remarks: WELL WAS PLUGGED DUE TO OPERATOR RELEASING THE LEASE.

Plugged through: TBG

District: 03

Signed _____

Quat

(TECHNICIAN)

NOV 21 2016

No

Form CP-2/3