

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23834-00-00
Spot: W2NENWNE Sec/Twnshp/Rge: 22-25S-12W
4923 feet from S Section Line, 1895 feet from E Section Line
Lease Name: NICHOLS 'A' Well #: 1
County: STAFFORD Total Vertical Depth: 4275 feet

Operator License No.: 34674
Op Name: H & D EXPLORATION LLC
Address: 165 WEST 1ST PO BOX 387
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3670		WITH 2 SX CMT
PROD	5.5	4260	0	WITH 230 SX CMT
SURF	8.625	662		WITH 380 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/07/2016 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: MITCH DRISCOLL Company: H & D EXPLORATION Phone: (620) 653-4791

Proposed Plugging Method: SET CIBP AT 3670' & 2 SX CMT. PERFORATE AT 700'. CIRCULATE CMT INSIDE & OUT. CHECK BACKSIDE.

Plugging Proposal Received By: LARRY HARRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/07/2016 1:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

Perfs:

SET CIBP @ 3670' WITH 2 SX CMT ON TOP. PERFORATE 5 1/2" CASING AT 700'. ESTABLISH CIRCULATION WITH FRESH WATER. CIRCULATE CMT TO SURFACE USING 160 SX CMT.


Top	Bot	Thru	Comments
4000	4002		
3721	3729		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

Signed


JA
(TECHNICIAN)

RECEIVED
NOV 10 2016
KCC DODGE CITY

NOV 21 2016 Form CP-2/3

720