

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

FINNEY County, Sec. 28 Twp. 22 Rge. 33 (X) (W)

Location as "NE/CNW%SW%" or footage from lines NW NE SW
Lease Owner LONITA OIL CORPORATION, INC.
Lease Name DAMME B Well No. 2
Office Address 704 BITTING BUILDING, WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed SEPTEMBER 7 1963
Application for plugging filed SEPTEMBER 7 1963
Application for plugging approved SEPTEMBER 10 1963
Plugging commenced SEPTEMBER 7 1963
Plugging completed SEPTEMBER 7 1963
Reason for abandonment of well or producing formation DRY HOLE

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well HUGH SCOTT, SUBLETTE, KANSAS
Producing formation NONE Depth to top Bottom Total Depth of Well 4822 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	375'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

8-5/8" SURFACE, COMMON CEMENT CIRCULATED
100 SACKS COMMON CEMENT DISPLACED THRU DRILL PIPE AT 2700' TO 2400'
2400' TO 375' WITH 48 VISCOSITY MUD 9 CC WATER LOSS
GLOBE PLUG PLACED AT 375' AND 35 SACKS COMMON CEMENT DISPLACED
GLOBE PLUG PLACED AT 40' AND 15 SACKS COMMON CEMENT DISPLACED
8-5/8" CASING CUT OFF AND WELDED SHUT.

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1963

9-13-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
R. E. HARTMAN (XXXXXXXXXX) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *R. E. Hartman*
704 BITTING BUILDING, WICHITA, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 11TH day of SEPTEMBER, 1963

Thomas H. Rippe
Notary Public.

My commission expires NOVEMBER 28, 1964

CERTIFIED DRILLER'S LOG

COMPANY: Lonita Oil Corporation, Inc.
 CONTRACTOR: Lonita Oil Corporation, Inc.
 COMMENCED: August 19, 1963
 COMPLETED: September 7, 1963
 ELEVATION: 2893' R.B.
 LEASE: Damme #B-2
 LOCATION: NW NE SW, 28-22S-33W, Finney County, Kansas
 CASING RECORD: 375' 8-5/8, cem. with 275 sacks
 Dry and Abandoned

<u>FORMATION</u>	<u>DEPTH</u>
Shale, Shells and Sand	0 - 375
Shale, Sand and Red Bed	375' - 1370
Sand and Shale	1370 - 1475
Sand	1475 - 1780
Shale and Anhydrite	1780 - 2052
Shale	2052 - 2310
Shale and Shells	2310 - 2440
Shale and Anhydrite	2440 - 2449
Shale and Lime	2449 - 3289
Shale and Lime with Chalky Streaks	3289 - 3562
Lime and Chalk	3562 - 4268
Lime	4268 - 4822
RTD	4822

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.


 R. E. HARTMAN

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 10th day of September, 1963.


 NOTARY PUBLIC

My Commission Expires: November 28, 1964