


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15 009 06956 0000
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County, Sec. 25 Twp. 16 Rge. 11 (X) (W)

Location as "NE/CNW/SW" or footage from lines SE SW SE
Lease Owner L. E. Phillips, Jr.
Lease Name Breford Well No. 1
Office Address 1407 Union National Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed June 6 1959
Application for plugging filed June 6 1959
Application for plugging approved June 6 1959
Plugging commenced June 6 1959
Plugging completed June 6 1959
Reason for abandonment of well or producing formation barren

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3382 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	515	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 280'. Set bottom plug at 280' with 25 sacks cement. Top plug at 40' w/10 sacks cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1959
6-17-59
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor S & S Drilling Company
Address Box 194, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
L. E. Phillips, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. E. Phillips, Jr.*

SUBSCRIBED AND SWORN TO before me this 15th day of June, 19 59

(Address) *W. A. Palmer*
Notary Public.

My commission expires October 4, 1961

PLUGGING
FILE SEC 25 T. 16 R. 11W
BOOK PAGE 46 LINE 15

15009-06956-0000

WELL LOG
Breford # 1
SE-SW-SE 25-16-11
Barton County Kansas

Comm: 5-29-59
Comp: 6-5-59

Elevation 1882 DF

0 - 70 Surface clay, Post rock
70-380 Shale and Red Bed
380 - 490 Sand
490 - 515 Shale with Sand Streaks
515 - 1370 Shale, Red Bed
1370 - 1500 Shale and shell
1500 - 1870 Lime and shale
1870 - 2630 Shale and lime
2630 - 3382 Lime and shale
3382 R. T. D.

Formation Tops:
Heebner 2919

Douglas 2957
Brown Lime 3022
Lansing 3035
Conglomerate 3336
Arbuckle 3378

STATE OF KANSAS
COUNTY OF BARTON ss

T. D. Sweetman, partner of S & S Drilling Company, being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

T. D. Sweetman
T. D. Sweetman

Subscribed and sworn before me this 8th day of June, 1959.

Dick B. Evans
~~Wichita, Kansas~~ Dick B. Evans
Notary Public, Barton County

My Commission expires ~~April 27, 1961~~ May 9, 1963

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1959
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 25 T. 16 R. 11W2
BOOK PAGE 46. LINE 15