

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

RECEIVED

9-13-02

SEP 13 2002

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

API NUMBER 15 075 20141-00-00

LEASE NAME Cheatum

WELL NUMBER 1-14

660 Ft. from S Section Line

220 Ft. from E Section Line

SEC. 14 TWP 22 RGE. 42W (E) or (W)

COUNTY Hamilton

Date Well Completed 04/16/77

Plugging Commenced 08/14/02

Plugging Completed 08/14/02

LEASE OPERATOR Chesapeake Operating, Inc.

ADDRESS P. O. Box 18496, Oklahoma City, OK 73154-0496

PHONE# (409) 848-8000 OPERATORS LICENSE NO. 32334

Character of Well X Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 02/26/02 (date)

by David P. Williams / Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Winfield Depth to Top 2597 Bottom 2608 T.D. 2668'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
MIRU Superior WS & Rosel Co., pump down tbg 400# hulls, cont w/20 sx cmt, squeeze off perforations @2597-2608', run inside of tbg, cut off tbg @520', POOH w/tbg, run punch log 520'-ground level, TOC @36', tie on the 8-5/8" bump down 3 sx cmt, 1W w/50#, RU RIH tbg to 515', cmt down tbg w/40 sx cmt, pull tbg out, top off 4-1/2" csq w/10 sx cmt, RDMO

Name of Plugging Contractor Allied Sementing Co., Inc. License No. _____

Address P. O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chesapeake Operating, Inc.

STATE OF OK COUNTY OF Oklahoma, ss.

Randy Gasaway, Chesapeake Operating, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Randy Gasaway
Randy Gasaway
(Address) P.O. Box 18496, Okla. City, OK
73154-0496

SUBSCRIBED AND SWORN TO before me this 11th day of September, 19 2002

Ornie B. Turner
Notary Public

My Commission Expires: September 2, 2004

OR

ALLIED CEMENTING CO., INC. 11807

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31
RUSSFEL, KANSAS 67665

SERVICE POINT:

Oakley

DATE <u>8-14-02</u>	SEC. <u>14</u>	TWP. <u>22s</u>	RANGE <u>42W</u>	CALLED OUT	ON LOCATION	JOB START <u>7:00 AM</u>	JOB FINISH <u>6:00 PM</u>
LEASE <u>Chester</u>	WELL # <u>1-14</u>	LOCATION <u>Sycamore 10.1 80' N W</u>			COUNTY <u>Abilition</u>	STATE <u>Ks</u>	

OLD OR NEW (Circle one)

CONTRACTOR Superior Servicing Inc. OWNER Same

TYPE OF JOB Plug old Hole

HOLE SIZE _____ T.D. _____

CASING SIZE 4 1/2" DEPTH _____

TUBING SIZE 2" DEPTH 520'

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX 1800' MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

CEMENT

AMOUNT ORDERED

350 sks 60/40 702 6% Gel

Used 70sk cement 2sk Hulls

COMMON	<u>42 sks</u>	@ <u>7.85</u>	<u>329.70</u>
POZMIX	<u>28 sks</u>	@ <u>3.55</u>	<u>99.40</u>
GEL	<u>4 sks</u>	@ <u>10.00</u>	<u>40.00</u>
CHLORIDE		@	
<u>Hulls</u>	<u>2 sks</u>	@ <u>18.00</u>	<u>36.00</u>
		@	
		@	
		@	
		@	
HANDLING	<u>370 sks</u>	@ <u>1.10</u>	<u>407.00</u>
MILEAGE	<u>49 sk/mile</u>		<u>962.00</u>

EQUIPMENT

PUMP TRUCK # 191 CEMENTER Dean
HELPER Andrew

BULK TRUCK # 357 DRIVER JLM

BULK TRUCK # 361 DRIVER L.22y

RECEIVED

SEP 13 2002

TOTAL 1874.10

REMARKS:

Trak mix Rate Mix 200' Hulls
followed w/ 70sk cement, Disp 2 bbls
locked up at 1800'. Shot Tub off
9T 520'. Pallet Tub out ran Band
Log. Press up 48' no cement. Ran
Tub to 520'. Mix 40 sk + cement
circulated. Pull Tub + Top off
w/ 10 sks Thank you

KCC WICHITA SERVICE

DEPTH OF JOB	
PUMP TRUCK CHARGE	<u>225.00</u>
EXTRA FOOTAGE	@ _____
MILEAGE <u>6.5 miles</u>	@ _____ <u>N/C</u>
PLUG	@ _____
	@ _____
	@ _____
TOTAL	<u>225.00</u>

CHARGE TO: Chesapeake Operating

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

	@ _____
	@ _____
	@ _____
	@ _____
	@ _____
TOTAL	_____

To Allied Cementing Co., Inc. _____

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE 2079.10

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Dennis Frick

PRINTED NAME