

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-075-10004-0000

API NUMBER Spud 6-17-63

LEASE NAME Combs Gas Unit

WELL NUMBER 1

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 1 TWP. 22 SRGE. 42 W (E) or (W)

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR M M Energy, Inc.

ADDRESS 2601 Northwest Expressway, Suite 904E, Oklahoma City, OK 73112 COUNTY Hamilton

PHONE # (405) 842-1666 OPERATORS LICENSE NO. 31409 Date Well Completed 7-1-63

Character of Well Gas Plugging Commenced 5-13-98

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed 5-14-98

The plugging proposal was approved on 5-26-98 (verbal 5-12-98) (date)

by Steve Durant, District # 1 (KCC District Agent's Name).

Is ACO-1 filled?          If not, is well log attached?         

Producing Formation Winfield Depth to Top 2723 Bottom T.D. 2768

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	206	8 5/8"	1963	none
Winfield Lime	Gas & Salt Water	surface	2766	4 1/2"	1963	none

Describe in detail the manner in which the well was plugged, indicating where the mud/fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. pumped 303 sks to balance from 2210' to 1720' via tbg - perf 4 shots @ 1200' - circ hole full (60 sks) via tbg from 1210' to surface & pumped additional 43 sks via 4 1/2" csg & squeezed off @ 600# psi - pumped 137 sks via 8 5/8" - 4 1/2" annulus

6-4-98

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cement Co. License No. none Required

Address P.O. Box 27, Oakley, Kansas 67748

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: M M Energy, Inc.


STATE OF Oklahoma COUNTY OF Oklahoma, ss.

M M Energy, Inc. Mike Murphy (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature] M M ENERGY, INC.  
 2601 NW EXPRESSWAY  
 SUITE 904E  
 OKLAHOMA CITY, OK 73112

(Address) [Address]

SWORN TO before me this 2nd day of June, 1998



[Signature]  
 Notary Public

Commission Expires: 3-28-01