

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-075-19007-0000

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

API NUMBER N/A
LEASE NAME HCU
WELL NUMBER 3421-D
3300 Ft. from S Section Line
3300 Ft. from E Section Line
SEC. 34 TWP. 22 RGE. 41 (E) or (W)
COUNTY Hamilton
Date Well Completed 7/1/64
Plugging Commenced 6/29/88
Plugging Completed 6/29/88

LEASE OPERATOR Plains Resources Inc.

ADDRESS 1601 N. W. Expressway, Oklahoma City, OK 73118

PHONE# (405) 842-2008 OPERATORS LICENSE NO. 05236

Character of Well Piggyback SWDW

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 19, 1988 (date)
by Shari Feist (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation Inj. zone Depth to Top 1310' Bottom 1330' T.D. 1336'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	From	To	Size	Put In	Pulled out
Surf.	83'	10 3/4"	83'	None	
Surf.	1336'	2 1/16"	1336'	None	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. KCC Commissioner on location. MI Hub, Dowell & RU Patrick. Tally in hole w/1" tbq to 1302' Top of perfs @ 1310'. Pmp 3 BFW & 25 sx CL H cmt mixed @ 15.6 ppg. Had partial returns of FW, perfs taking cmt. SD. TOH w/tb. WOC 4 hrs. TIH w/33 jts 1" tbq to TOC @ 690'. Pmp 25 sx CL H cmt to surf. POH w/1" tbq. RD Dowell, Patrick & Hub. 3421-D Piggyback PSA

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Plugged by Operator License No. 05236

Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Plains Resources Inc.

STATE OF OKLAHOMA COUNTY OF Oklahoma, ss.

Michael R. Whitaker, Prod. Eng. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael R. Whitaker

(Address) 1601 NW Expressway, OKC, OK 73118

SUBSCRIBED AND SWORN TO before me this 26 day of Sept, 1988

My Commission Expires: 9-10-90 Gence Cooley Goodness Notary Public

