

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Dunne Equities Operating, Inc.

ADDRESS 8100 E. 22<sup>ND</sup> STREET N. #1100 WICHITA, KS 67226

PHONE# (316) 684-6508 OPERATORS LICENSE NO. 32166

Character of Well DATA

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed DELAYED

Plugging Commenced 3-20-2000

Plugging Completed 3-21-2000

The plugging proposal was approved on 3-20-2000 (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

RECEIVED  
 STATE CORPORATION COMMISSION

Producing Formation N/A Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

4-10-00  
 CONSERVATION DIVISION  
 Wichita Kansas

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>SURFACE</u>		<u>SURFACE</u>	<u>318</u>	<u>8 7/8</u>	<u>318</u>	
<u>PRODUCTION</u>						
<u>PRODUCTION</u>		<u>SURFACE</u>	<u>2872</u>	<u>5 1/2</u>		<u>801</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.  
Mixed 2 sx hulls & 25 sx cement to plug perfs from 2626 to 2426. Rec. 801 5 1/2 & pulled to 770. Circ hole w/mud & mixed 40 sx from 770 to 650. 40 sx 340 to 220 10 sx 40 to 0 Cut off & capped 8 7/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: DUNNE EQUITIES OPERATING, INC

STATE OF KANSAS COUNTY OF SEDGWICK, SS.

Alonzo M. Permistead (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Alonzo M. Permistead

(Address) 8100 E 22<sup>ND</sup> ST. N. #1100 WICHITA 67226

SUBSCRIBED AND SWORN TO before me this 6<sup>th</sup> day of April, 19 2000

Alexis R. Wood  
 Notary Public

My Commission Expires: \_\_\_\_\_

