

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-055-20,129-0000

LEASE NAME Norman Adams

WELL NUMBER #1

1980 Ft. from S Section Line

1980 Ft. from W Section Line

SEC. 4 TWP. 22S RGE. 33W (E) or (W)

COUNTY Finney

Date Well Completed _____

Plugging Commenced 3-18-93

Plugging Completed 3-22-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Rama Operating Company, Inc.

ADDRESS P.O. box 159 Stafford, Ks. 67578

PHONE# (316)234-5191 OPERATORS LICENSE NO. 3911

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 4785'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	793'	none
				5-1/2"	4785'	1100'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 4650' and 5 sacks cement. Shot pipe @2800', 1600' and 1100', set 50 sacks @1100', set 70 sacks @800', set 25 sacks @400', circulated from 40' to surface with 15 sacks cement, 60/40 pos, 6% gel.

Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rama Operating Company, Inc.

STATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso (Employee of Operator) of Wichita, Kansas
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 25th day of March, 1993

My Commission Expires: _____



Form CP-4
Revised 05-88