

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 5-009-15074-0000

LEASE NAME VA/ENTA
Dealanta #3

WELL NUMBER SW NW NE

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 31 TWP. 16 RGE. 11w (N) or (W) (W)

COUNTY Barton

Date Well Completed

Plugging Commenced 5/17/85

Plugging Completed 5/30/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR N.C.R.A.

ADDRESS Box 1404, McPherson, Ks. 67460

PHONE#(316) 241-2340 OPERATORS LICENSE NO.

Character of Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3182'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	238'	none
				5 1/2"	3164'	1708'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 2900' & 5 sacks cement. Shot pipe at 2500', 2100', 1900', & 1708'. Pulled 52 joints of pipe. Plugged well with 4 hulls, 25 cement, 12 gel, 40 cement, 3 gel, 1 hull, plug, & 100 sacks 50/50 poz 6% gel 3% c.c. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling

RECEIVED
LIBRARY NO. 6050
STATE CORPORATION COMMISSION

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice JUN 05 1985 06-05-85
, ss.

R. Darrell Kelso (Employee of Operator) of Conservation Division (Operator) of Wichita, Kansas above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 3rd day of June, 1985

My Commission Expires:



Notary Public

COMPANY: Black-Marshall Oil Company
CONTRACTOR: Black-Marshall Oil Company

FARM: Valenta #3
LOCATION: SW NW NE 31-16-11W
Barton County, Kansas

COMMENCED: 3-7-47
COMPLETED: 3-19-47

CASING RECORD:
8 5/8" @ 230 = 90 oke
5 1/2" @ 3182 = 125 oke

ELEVATION: 1911
PRODUCTION:


Formations	Depth
Post Rock Sand	75
Shale and Shells	150
Sand	205
Shale and Shells	500
Shale, shells and Redbed	680
Shale and Redbed	740
Anhydrite	765
Shale and Shells	1165
Salt	1385
Shale and Lime	1800
Lime	1880
Bro. Lime	1950
Shale and Lime	2050
Shale and Shells	2165
Shale	2305
Shale and Lime	2705
Lime	2765
Bro. Lime	2825
Lime	2905
Lime and Shale	2990
Lime	3035
Shale and Lime	3090
Lime	3160
Quartzite	3182
ROTARY TOTAL DEPTH	3182

<u>TOPS</u>	
Anhydrite	740
Topoka	2660
Kansas City	3012
Quartzite	3153

STATE OF KANSAS)
COUNTY OF BARTON) SS

We hereby certify this to be a correct and accurate log of the above described well as shown by the daily drilling reports.

BLACK-MARSHALL OIL COMPANY


Lock F. Huff, Vice President

Subscribed and sworn to before me this 26th day of March, 1947.


Notary Public

My commission expires February 19, 1949.