

1080414

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,207-0000

C NE NW, SEC. 24, T 22 S, R 25 (W) X

4620 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Lease Name Bohling Well # 1

Operator: Vincent Oil Corporation

County Hodgeman 152.00

Name & Address 125 North Market, Suite 1110

Well Total Depth 4677 Mississippi feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 601

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Wheatstate Oilfield Services, Inc. License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 12:30 pm Day: 1 Month: September Year: 1985

Plugging proposal received from Tony Ernst

(company name) Wheatstate (phone) 316-672-7514

Elevation N/A

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1340-91'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 75 sx cement

3rd plug 40' out of the surface pipe with 50 sx cement

solid bridge - hulls - plug at 40' -- cement to surface with 10 sx

4th plug cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by J. H. Mead

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:00 pm Day: 1 Month: September Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 1700' with 50 sx cement, 2nd plug at 1400' with 75 sx

cement, 3rd plug at 700' with 50 sx cement, 4th & 5th plugs - solid bidge- hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx

cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 6 1985 9-6-85

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (copy) observe this plugging.

CONSERVATION DIVISION
Wichita, Kansas

DATE SEP 10 1985

Signed J. H. Mead (TECHNICIAN)

INV. NO. 10017
9-1FORM CP-2/3
Rev. 01-84