

15-055-00001-0000

1 070145

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 10-24-52

NE NE NE, SEC. 21, T. 22 S, R. 31 (W)E
4950 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4186

330 feet from E section line

Operator: Austin Brady
Name & Address: P. O. Box 793
Garden City, KS 67846

Lease Name Sonderregger Well # 1

County Finney

Well Total Depth 4970 161.53 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P. O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 3:30 pm Day: 24 Month: February Year: 19 86

Plugging proposal received from Austin Brady

(company name) Austin Brady (phone) 316-276-6928

were: 5 1/2" at 4968' Perfs at 4705-48'DV at 3080' Pump through 5 1/2" casing with mud between plugs

1st plug pump 50 sx cement to bottom through tubing

2nd plug pump 50 sx cement at 3150' through tubing

3rd plug perforate 5 1/2" casing at 1150' and pump 40 sx cement

4th plug pull to 340' and pump 50 sx cement

5th plug pull casing and pump 10 sx cement to surface

Plugging Proposal Received by Don Ubel

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 4:30 pm Day: 24 Month: February Year: 19 86

ACTUAL PLUGGING REPORT Pumped 1st two plugs through tubing and pumped last plugs through 5 1/2 casing with mud between plugs. 1st plug pumped 50 sx cement at 3830', 2nd plug at 3150' with 50 sx cement, 3rd plug perforated 5 1/2" casing at 1150 and pumped 40 sx cement, 4th plug pulled to 340' and pumped 50 sx cement, 5th plug pulled casing and pumped 10 sx cement to surface.

Remarks: Recovered 755' 5 1/2" casing. Used common cement by Sargent's.

(If additional description is necessary, use BACK of this form.)

(did not observe this plug) INVOICED

STATE CORPORATION COMMISSION

Signed Dan Goodwin (TECHNICIAN)

MAR 11 1986

DATE MAR 12 1986

INV. NO. 12913 2-24

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84