

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-02479-00-00
Spot: SE Sec/Twnshp/Rge: 26-23S-17E
1890 feet from S Section Line, 275 feet from E Section Line
Lease Name: MENTZER HOLTZ Well #: 11
County: ALLEN Total Vertical Depth: 1000 feet

Operator License No.: 5983
Op Name: LEIS, VICTOR J.
Address: PO BOX 223
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	1000		120 SX
SURF	10	20		10 SX

Well Type: EOR UIC Docket No: E13321.1 Date/Time to Plug: 10/18/2016 12:00 AM
Plug Co. License No.: 32079 Plug Co. Name: LEIS, JOHN E.
Proposal Rcvd. from: VICTOR J. LEIS Company: Phone: (913) 285-0127

Proposed Plugging Method: PUMP 50' CEMENT PLUG AT BOTTOM PERFS, THEN PUMP A 50' CEMENT PLUG AT THE K.C. LIME, THEN PUMP CEMENT PLUG FROM 200' TO SURFACE.

Plugging Proposal Received By: Witness Type: NONE
Date/Time Plugging Completed: 10/25/2016 10:00 AM KCC Agent: RYAN DULING

Actual Plugging Report: Perfs:

Ran 1" pipe down the inside of the 2" casing cemented inside the 6.25" casing to TD. Pumped and placed a 50' cement plug at TD. Pulled 1" pipe to 550'. Pumped and placed a 50' cement plug at 550'. Pulled 1" pipe up to 200'. Pumped and circulated cement from 200' to surface. A total of 10 sacks of portland cement was reported used to plug this well.

RECEIVED
KCC DIST # 3
NOV 08 2016
CHANUTE, KS

RD

Remarks:
Plugged through: TBG

District: 03 Signed: [Signature] E.C.R.S.
(TECHNICIAN)

KCC WICHITA
NOV 14 2016
RECEIVED

11-14-16

NOV 21 2016 Form CP-2/3
700
cc uic