

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-141-00054-00-01  
Spot: SWSWNW Sec/Twshp/Rge: 14-8S-14W  
2972 feet from S Section Line, 4926 feet from E Section Line  
Lease Name: BALES Well #: 2  
County: OSBORNE Total Vertical Depth: 750 feet

Operator License No.: 5610  
Op Name: BRUCE OIL COMPANY, L.L.C.  
Address: 1704 LIMESTONE RD  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	8.625	241		175 sx
PROD	2.375	605		72 SX
SURF	3.5	858		200 SX

Well Type: SWD UIC Docket No: D17029.0 Date/Time to Plug: 10/04/2016 8:30 AM  
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC  
Proposal Rcvd. from: LEVI KOEHN Company: BRUCE OIL COMPANY Phone: (620) 241-2938

Proposed Plugging Method: Ordered 100 sx 60/40 pozmix 4% gel cement.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/04/2016 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Tagged bottom at 605'. Pulled up to 601'. Hooked to 1" tubing and pumped 20 sx cement. Circulated cement from bottom to top. POOH. Hooked to 2.375" casing and pressured to 250 psi with 5 sx cement. Witnessed circulation of 3.5" casing.

GPS: 39.35898 -098.85910

Perfs:

Top	Bot	Thru	Comments
620	630		

Remarks: QUALITY CEMENTING TICKET # 1792

Plugged through: TBG

District: 04

Signed

*Ray Dinkel*

(TECHNICIAN)

CM

KCC WICHITA

OCT 31 2016

RECEIVED

NOV 21 2016

*no cc uic*

Form CP-2/3

OCT 10 2016