

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-27940-00-00
Spot: SEWNNE Sec/Twnshp/Rge: 17-26S-19E
4290 feet from S Section Line, 1650 feet from E Section Line
Lease Name: J JARRED Well #: 3W
County: ALLEN Total Vertical Depth: 885 feet

Operator License No.: 31280
Op Name: BIRK, BRIAN L. DBA BIRK PETROLEUM
Address: 874 12TH RD SW
BURLINGTON, KS 66839

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.375	885		95 SX
SURF	6	20		5 SX

Well Type: EOR UIC Docket No: E25415.3 Date/Time to Plug: 10/25/2016 12:00 AM
Plug Co. License No.: 31280 Plug Co. Name: BIRK, BRIAN L. DBA BIRK PETROLEUM
Proposal Rcvd. from: BIRK PETROLEUM Company: Phone: (620) 364-1311

Proposed Plugging Method: Set 50' plug at TD. Set 50' plug at base of the Kansas City. Set solid plug 200' to surface.

Plugging Proposal Received By: WitnessType: NONE
Date/Time Plugging Completed: 10/25/2016 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:
Ran 1" pipe down the inside of the 2.375" that was cemented inside the 6" surface casing to TD. Pumped and circulated cement through the 1" pipe inside the 2.375" casing from TD to surface. Pulled the 1" pipe out of the well and topped the well off with cement. A total of 60 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
856	868		

RECEIVED
KCC DIST # 3
NOV 08 2016
CHANUTE, KS
RD

Remarks:
Plugged through: TBG

District: 03 Signed: [Signature] E.C.A.S.
(TECHNICIAN)
KCC WICHITA
NOV 14 2016 RECEIVED
NOV 21 2016 Form CP-2/3
no cc ulc