

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-24535-00-01  
Spot: NESWNE Sec/Twnshp/Rge: 6-11S-20W  
3654 feet from S Section Line, 1756 feet from E Section Line  
Lease Name: RICHARDS Well #: 3  
County: ELLIS Total Vertical Depth: 3658 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		3040		PACKER TYPE AND SETTING DEPTH: HALLIBURTON R-4 SET @ 3040'
PROD	5.5	3657		
SURF	8.625	258		
T1	2.375	3050		

Well Type: EOR UIC Docket No: E28024.1 Date/Time to Plug: 10/27/2016 11:30 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: KENT WILSON Company: MAI OIL OPERATIONS Phone:

Proposed Plugging Method: Had tubing leak and multiple holes in casing.  
Perforated @ 1490' - Circulated with 300 sx cement

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE  
Date/Time Plugging Completed: 10/27/2016 2:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran tubing to 3510'  
Pumped 150 sx 60/40 4% gel cement with 250# hulls  
Pulled to 2050'  
Pumped 140 sx cement with 250# hulls  
Pulled to 520'  
Circulated with 60 sx cement  
Topped off casing with 10 sx cement  
Pumped 10 sx down backside. SIP 200 psi

Perfs:

Top	Bot	Thru	Comments
3648	3652		
3643	3656		
3497	3501		
3483	3487		
3463	3466		
3408	3411		
3236	3240		
3107	3111		

Received  
KANSAS CORPORATION COMMISSION  
**NOV 18 2016**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: TBG

NOV 21 2016  
MCC UIC

District: 04

Signed

Case Morris

(TECHNICIAN)