

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-147-20682-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 21-5S-20W
330 feet from S Section Line, 330 feet from W Section Line
Lease Name: HANSEN Well #: 1
County: PHILLIPS Total Vertical Depth: 3688 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3685		145 SX
SURF	8.625	209		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/06/2016 9:00 AM
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 14 sx gel and 300 # hulls.
PC 1723' to surface w/250 sx cement.
Production perforations: 3612' - 3627'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/06/2016 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3600' and pumped 14 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1740' and pumped 180 sx cement to circulate cement to surface. Pulled all tubing and topped off 5 1/2" casing w/20 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 5 sx cement. Shut in pressure 300 psi.

GPS: 39.59729N -099.58904W

Perfs:

Top	Bot	Thru	Comments
3622	3627		
3612	3616		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1795

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

KCC WICHITA

OCT 31 2016

RECEIVED

NOV 21 2016

710

CM

Form CP-2/3

OCT 11 2016