

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-137-20679-00-00
Spot: NWSENWSE Sec/Twnshp/Rge: 36-3S-24W
1815 feet from S Section Line, 1815 feet from E Section Line
Lease Name: LAWSON D Well #: 1
County: NORTON Total Vertical Depth: 3820 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3820		145 SX
SURF	8.625	289		180 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2016 10:00 AM
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 13 sx gel (100 #) and 300 # hulls.
Port Collar at 1986' w/350 sx cement (did not circulate).
Production perforations: 3733' - 3742'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/05/2016 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3700' and pumped 13 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1770' and pumped 180 sx cement to circulate cement to surface. Pulled all tubing. Topped 5 1/2" casing with 20 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 90 sx cement. Shut in pressure 300 psi.

GPS: 39.74565N -099.97112W

Perfs:

Top	Bot	Thru	Comments
3733	3742		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1793

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

KCC WICHITA

NOV 21 2016

OCT 31 2016

no

Form CP-2/3

OCT 16 2016

RECEIVED