

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-02719-00-02
Spot: NESESE Sec/Twnshp/Rge: 31-8S-24W
1073 feet from S Section Line, 225 feet from E Section Line
Lease Name: HOLLEY Well #: 8-2
County: GRAHAM Total Vertical Depth: 3947 feet

Operator License No.: 34402
Op Name: GARAL, DONNA AND VINCENT INNON
Address: 30-38 48 ST
ASTORIA, NY 11103

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3947		250 SX
SURF	8.625	249		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/14/2016 11:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: JASON DINGES Company: VJI NATURAL RESOURCES Phone: (785) 623-8060

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 600 # hulls and 12 sx gel.
DV Tool at 2139' w/275 sx cement.
Perforations at 3893' - 3903' and 3910' - 3916'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/24/2016 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3640' and pumped 12 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 2178' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1206' and pumped 100 sx cement. Good circulation of cement. Pulled tubing out and topped off with 10 sx cement. Tied on to backside and squeezed with 85 sx cement. Shut in pressure 150 psi.

GPS: 39.30859 -100.03391

Perfs:

Top	Bot	Thru	Comments
3910	3916		
3893	3903		

Received
KANSAS CORPORATION COMMISSION
NOV 18 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: GLOBAL CEMENT TICKET # 2755 & 2726

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

cm

NOV 21 2016

no

Form CP-2/3

OCT 26 2016