

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-02837-00-02
Spot: NWSWNW Sec/Twnshp/Rge: 5-9S-24W
3630 feet from S Section Line, 4950 feet from E Section Line
Lease Name: HOLLEY UNIT Well #: 14-4
County: GRAHAM Total Vertical Depth: 4000 feet

Operator License No.: 34402
Op Name: GARAL, DONNA AND VINCENT INNON
Address: 30-38 48 ST
ASTORIA, NY 11103

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4000		75 SX
SURF	8.625	197		115 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/18/2016 9:30 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: JASON DINGES Company: VJN NATURAL RESOURCES Phone: (785) 623-8060

Proposed Plugging Method: Ordered 435 sx 60/40 pozmix 4% gel cement, 10 sx gel and 600 # hulls.
DV Tool at 2139' w/275 sx cement.
Perforations: 3957' - 3963' and 3977' - 3981'.
Tagged hard at 3142' and could not wash down.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/24/2016 12:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3142' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 2428' and pumped 175 sx cement w/200 # hulls. Pulled tubing to 1730' and pumped 150 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 25 sx cement. Tied on to backside and squeezed with 60 sx cement and 100 # hulls.
10/24/2016 - Tied on to backside and squeezed with 10 sx cement . Shut in pressure 250 psi.
GPS: 39.30132 -100.03183

Perfs:

Top	Bot	Thru	Comments
3977	3981		
3957	3963		


Received
KANSAS CORPORATION COMMISSION
NOV 18 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: GLOBAL CEMENT TICKET # 2721

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

OCT 26 2016

NOV 21 2016

700

Form CP-2/3