

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-22928-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 31-8S-24W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HOLLEY Well #: 8-A
County: GRAHAM Total Vertical Depth: 4035 feet

Operator License No.: 34402
Op Name: GARAL, DONNA AND VINCENT INNON
Address: 30-38 48 ST
ASTORIA, NY 11103

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4035		450 SX
SURF	8.625	204		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/26/2016 10:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: JASON DINGES Company: VJI NATURAL RESOURCES Phone: (785) 623-8060

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls and 10 sx gel.
Alt II circulated with 450 sx cement.
Perforations: 3924' - 3927', 3945' - 3948'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/26/2016 11:15 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 75 sx cement w/200 # hulls followed by 10 sx gel, followed by 220 sx cement w/100 # hulls. Shut in pressure 400 psi. Topped off casing with 10 sx cement. Tied on to backside and pumped 5 sx cement. Shut in pressure 250 psi.

GPS: 39.31171 -100.04083

Perfs:

Top	Bot	Thru	Comments
3970	3974		SPF
3965	3968		SPF
3945	3948		SPF
3924	3927		SPF

Received
KANSAS CORPORATION COMMISSION
NOV 18 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: GLOBAL CEMENT TICKET # 2759

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

CM

NOV 02 2016

NOV 21 2016

Form CP-2/3