

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-02724-00-00
Spot: SWNESE Sec/Twnshp/Rge: 31-8S-24W
1650 feet from S Section Line, 990 feet from E Section Line
Lease Name: HOLLEY Well #: 8-7
County: GRAHAM Total Vertical Depth: 3990 feet

Operator License No.: 34402
Op Name: GARAL, DONNA AND VINCENT INNON
Address: 30-38 48 ST
ASTORIA, NY 11103

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3960		150 SX
SURF	8.625	200		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/24/2016 9:30 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: JASON DINGES Company: VJI NATURAL RESOURCES Phone: (785) 623-8060

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.
DV Tool at 2128' w/300 sx cement.
Perforations at 3419' - 3925'.
Hit fish at 1720' and cannot drill through. District supervisor approved plugging from 1720'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/24/2016 11:55 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1720' and pumped 170 sx cement. Good circulation of cement. Pulled tubing out and topped off with 30 sx cement. Tied on to casing and squeezed with no cement. Shut in pressure 225 psi. Tied on to backside and squeezed with 115 sx cement and 200 # hulls. Shut in pressure 50 psi.

GPS: 39.31046 -100.03626

Perfs:

Top	Bot	Thru	Comments
3919	3925		
3419	3925		

Received
KANSAS CORPORATION COMMISSION
NOV 18 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: GLOBAL CEMENT TICKET # 2724

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN) CR

NOV 21 2016
NO

OCT 26 2016