

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-187-20881-00-00
Spot: SE Sec/Twnshp/Rge: 30-27S-40W
1256 feet from S Section Line, 1303 feet from E Section Line
Lease Name: FRASER Well #: 2-30R
County: STANTON Total Vertical Depth: 2560 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2128		
PROD	5.5	2560	0	WITH 500 SX CMT
SURF	8.625	671		WITH 327 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/08/2016 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JASON PHELPS Company: LINN OPERATING Phone: (281) 840-4000

Proposed Plugging Method: CIBP @ 2128'. RELEASE FROM CIBP @ PUMP 110 SX CMT. RTOH TO 1050' & CIRCULATE TO SURFACE WITH 110 SX CMT. CHECK BACKSIDE WITH 10-20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/08/2016 12:30 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

Perfs:

CIBP @ 2128'. 1ST PLUG AT 2100' WITH 165 SX CMT. 2ND PLUG AT 500' WITH 50 SX CMT. TOPPED OFF WITH 15 SX CMT.

Top	Bot	Thru	Comments
2178	2271		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed [Signature]

(TECHNICIAN)

RECEIVED
NOV - 9 2016
KCC DODGE CITY

[Signature]

51A

NOV 21 2016
[Signature]

Form CP-2/3