

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-129-21684-00-00
Spot: NWSESE Sec/Twnshp/Rge: 8-31S-39W
1253 feet from S Section Line, 1219 feet from E Section Line
Lease Name: GILLESPIE Well #: 4
County: MORTON Total Vertical Depth: 2800 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2795	0	WITH 540 SX CMT
SURF	8.625	596		WITH 289 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/10/2016 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JASON PHELPS Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: TBG STUCK IN HOLE. CUT TBG AT 1700' & PUMP 75 SX CMT. TAG TOC WITH TBG THEN CIRCULATE CMT TO 0'.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2016 11:30 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

TBG STUCK IN HOLE. CUT TBG AT 2100' THEN PUMP 75 SX CMT WITH 250# HULLS. TAGGED TOC @ 1325'. PUMPED 90 SX CMT TO 0'. FILL BACKSIDE WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2428	2610		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed Kenny M. Sullivan
(TECHNICIAN)

RECEIVED
NOV 16 2016
KCC DODGE CITY

NOV 21 2016

Form CP-2/3

KMS