

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20645-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 26-23S-41W  
4049 feet from S Section Line, 1302 feet from E Section Line  
Lease Name: HCU Well #: 2631-B  
County: HAMILTON Total Vertical Depth: 2685 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2684	0	WITH 430 SX CMT
SURF	8.625	225		WITH 155 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/20/2016 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/26/2016 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

TBG AND RODS ARE STUCK IN THE HOLE. UNABLE TO FREE TBG OR BACK OFF RODS. RUN STRING SHOT BETWEEN THE 2 3/8" TBG & 4 1/2" CASING & BACKED OFF TBG AT 2139'. POOH WITH 66 JOINTS OF TBG WITH 58 RODS(1450') STUCK INSIDE. LEFT 14 JOINTS OF TBG & 44 3/4" RODS IN THE WELL. TOP OF ROD FISH AT 1458'. TOP OF TBG FISH IS 2139'. RUN TBG TO 1536' & SPOT 75 SX CMT WITH 250# HULLS. PULL TBG TO 1000'. LOAD HOLE WITH 14 BBLs. TOC IN 4 1/2" IS AT 900'. CIRCULATE CMT FROM 1000' TO 0' WITH 70 SX CMT. TOP OFF WITH 5 SX CMT. 10 SX CMT DOWN THE ANNULUS TO 300#.

Top	Bot	Thru	Comments
2514	2566		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: TBG

District: 01

Signed

*Ken Jehlik*  
SA

(TECHNICIAN)

RECEIVED  
OCT 31 2016  
KCC DODGE CITY

NOV 21 2016 Form CP-2/3

*no*